



Electrical Supplies Limited

CURRENT INSTALLATION

PROJECT REF: SELCO - CARDIFF

CURRENT INSTALLATION

AREA	QTY	CURRENT GEAR TYPE	C/W	T/W
				0
LOWBAYS	99	400W METAL HALIDE	400	39600
BATTENS	66	8FT SINGLE BATTEN	125	8250
BATTENS	16	6FT SINGLE BATTEN	70	1120
BATTENS	11	6FT TWIN BATTEN	140	1540
				0

ENERGY SAVING COMPARISON

PROPOSED INSTALLATION

BURNING Hr's p.a: 4498 PENCE PER kWh: £0.12

PROPOSED INSTALLATION

QTY	PROPOSED GEAR TYPE	C/W	T/W
			0
99	135W LED	135	13365
66	6FT LED BATTEN	46	3036
16	6FT LED BATTEN	46	736
11	6FT LED BATTEN	46	506
			0

TOTAL WATTS

50510

TOTAL WATTS

17643

RUNNING COST'S p.a

£27,263.28

RUNNING COST'S p.a

£9,522.99